Technical - Commercial Proposal

Yoseftal Eilat. Example Proposal 1. Shabbat option

ORAD-YOS-EX1-2026-10

IMPORTANT – THIS IS NOT A REAL, FORMAL OR OFFICIAL PROPOSAL. It is an example only, prepared to support the offer that Orad must make to the end client.

Sales Rep. : David Gutierrez
E-mail : dgutierrez@grupoace.es
Telephone : +34-661260789

www.advantecnia.com

Alex Jusid

IMPORTANT – THIS IS NOT A REAL, FORMAL OR OFFICIAL PROPOSAL. It is an example only, prepared to support the offer that Orad must make to the end client.

ACE Business Group International
C/ Colada de Pozuelo, 20
28925 Alcorcón, Madrid (ESPAÑA)
www.acebg.es
CIF: A83706721

CODE	SUMMARY	UNITS	QUANTITY	PRICE	AMOUNT
CHAPTER 01 Yoseftal Eilat. Example Proposal 1. Shabbat option					
SUBCHAPTER 0101 Nurse Call System					
ACE82012153	**ud 1-Module PVC panel, Nurse call (red) + Bayonet pigtail. Lc RJ** 1-Module PVC Panel, Nurse Call. LC AdvantCare PVC. Recessed plastic module with 1 button to request nurse presence in patient room. Round 30mm domed resin pushbutton with representative shape and colour (red RAL 3020), identification label "Nurse", and Braille text. LED signaling of use on button. Including female 5/8 pin Bayonet pigtail for connection of pear-type hand pushbutton. PVC panel, white RAL 9010, dimensions: 114*114*8 mm. Recessed wall mounting. Including fixing elements for wall box. LC electronics. LC I/0 communications with LCOM card, RJ45 connector. Reference ACE82012153EN, manufactured by Advantecnia.				
	ROOM 1	3			
	ROOM 2	3			
	ROOM 3	3			
	ROOM 4	3			
	ROOM 5	3			
	ROOM 6	3			
	ROOM 7	3			
	ROOM 8	3			
			24,00	67,13	1.611,12
ACE39060521	**ud 1-button bed handset, capacity button, 2m cable, white, Bayonet** 1-Button pear-type handset. Bed hand button with 1 button for nurse presence request in room. Capacitive button, with reassuring LED lighting, identifying drawing and colour, and Braille text. 2 Meters length cable, finished in Bayonet plug. Made of antibacterial plastic material. White cable and housing. Manufactured by Advantecnia, reference ACE39060521EN.				
	ROOM 1	3			
	ROOM 2	3			
	ROOM 3	3			
	ROOM 4	3			
	ROOM 5	3			
	ROOM 6	3			
	ROOM 7	3			
	ROOM 8	3			
			24,00	56,05	1.345,20

IMPORTANT – THIS IS NOT A REAL, FORMAL OR OFFICIAL PROPOSAL. It is an example only, prepared to support the offer that Orad must make to the end client.

ACE Business Group International
C/ Colada de Pozuelo, 20
28925 Alcorcón, Madrid (ESPAÑA)
www.acebg.es
CIF: A83706721

CODE	SUMMARY	UNITS	QUANTITY	PRICE	AMOUNT
ACE82082137	**ud 1-Module PVC panel, Presence / cancel (green). Lc RJ** 1-Module PVC Panel, Presence. LC AdvantCare PVC. Recessed plastic module with 1 button to marking nurse presence in patient room. Round 30mm domed resin pushbutton with representative shape, in green colour (RAL 6016) and 'presence' label. LED signaling of use on button. PVC panel, white RAL 9010, dimensions: 114*114*8 mm. Recessed wall mounting. Including fixing elements for wall box. LC electronics. LC I/0 communications with LCOM card, RJ45 connector. Reference ACE82082137EN, manufactured by Advantecnia.				
	ROOM 1 · ENTRANCE	1			
	ROOM 2 · ENTRANCE	1			
	ROOM 3 · ENTRANCE	1			
	ROOM 4 · ENTRANCE	1			
	ROOM 5 · ENTRANCE	1			
	ROOM 6 · ENTRANCE	1			
	ROOM 7 · ENTRANCE	1			
	ROOM 8 · ENTRANCE	1			
	BATHROOM 1 · OUTSIDE	1			
	BATHROOM 2 · OUTSIDE	1			
	BATHROOM 3 · OUTSIDE	1			
	BATHROOM 4 · OUTSIDE	1			
	BATHROOM 5 · OUTSIDE	1			
	BATHROOM 6 · OUTSIDE	1			
	BATHROOM 7 · OUTSIDE	1			
	BATHROOM 8 · OUTSIDE	1			
			16,00	67,13	1.074,08
ACE40320303	**ud SOS mechanism + Pullcord. Lc RJ** SOS mechanism. Advantcare 45x45. For SOS-Emergency alarm activation. Membrane-type pushbutton, with identifiable symbol, colour and label. LED use signalling, in pushbutton. Including an ergonomic plastic pull handle, with a 2-meter nylon cord and an anti-breakage device. LC I/0 communications with LCOM card. RJ12 connector. Recessed wall mounting. Frontal dimensions: 45*45 mm. Mounted on a white European-type frame (frontal dimensions: 80 * 80 mm). Manufactured by Advantecnia, reference ACE40320303EN.				
	BATHROOM 1 (WC + SHOWER)	2			
	BATHROOM 2 (WC + SHOWER)	2			
	BATHROOM 3 (WC + SHOWER)	2			
	BATHROOM 4 (WC + SHOWER)	2			
	BATHROOM 5 (WC + SHOWER)	2			
	BATHROOM 6 (WC + SHOWER)	2			
	BATHROOM 7 (WC + SHOWER)	2			
	BATHROOM 8 (WC + SHOWER)	2			
			16,00	44,10	705,60

ACE Business Group International
C/ Colada de Pozuelo, 20
28925 Alcorcón, Madrid (ESPAÑA)
www.acebg.es
CIF: A83706721

CODE	SUMMARY		UNITS	QUANTITY	PRICE	AMOUNT
EOP004	**ud Tricolor LED PCB**					
	Corridor / door light, 3 colours. Including LEGRAND mounting frame, cover plate and diffuser. Above each room door (corridor) and above each bathroom door.					
		ROOM 1	1			
		ROOM 2	1			
		ROOM 3	1			
		ROOM 4	1			
		ROOM 5	1			
		ROOM 6	1			
		ROOM 7	1			
		ROOM 8	1			
		BATHROOM 1	1			
		BATHROOM 2	1			
		BATHROOM 3	1			
		BATHROOM 4	1			
		BATHROOM 5	1			
		BATHROOM 6	1			
		BATHROOM 7	1			
		BATHROOM 8	1			
				16,00	128,57	2.057,12
	TOTAL SUBCHAPTER 0101 Nurse Call System					**6.793,12**

SUBCHAPTER 0102 Digital Room - Shabbat

ACE Business Group International
C/ Colada de Pozuelo, 20
28925 Alcorcón, Madrid (ESPAÑA)
www.acebg.es
CIF: A83706721

CODE	SUMMARY		UNITS	QUANTITY	PRICE	AMOUNT
ECV169	**ud PCB 24 pins 12-48V** Room controller, up to 5 alarm inputs and 1 light output. 12-48V DC. Installed in junction box near the call point. Bus 2x2x0.8 mm in daisy chain from SmartHub (RS485 + 12-48V). Two controllers per 3-bed room (A: 3 bed calls + presence / cancel + room light; B: 3 handset disconnection alarms) and one per bathroom (2 SOS + presence / cancel + bathroom light).					
		ROOM 1	2			
		ROOM 2	2			
		ROOM 3	2			
		ROOM 4	2			
		ROOM 5	2			
		ROOM 6	2			
		ROOM 7	2			
		ROOM 8	2			
		BATHROOM 1	1			
		BATHROOM 2	1			
		BATHROOM 3	1			
		BATHROOM 4	1			
		BATHROOM 5	1			
		BATHROOM 6	1			
		BATHROOM 7	1			
		BATHROOM 8	1			
				24,00	114,29	2.742,96
EVV049	**ud SmartHub connectia** System server and head of the room controllers bus. 19" 1U, 230 VAC input, 12-48V DC output. One per ward section.					
		MAIN RACK	1			
				1,00	928,57	928,57
EOP006	**ud Video local server & Notifications or LVNS** Local server and notifications: manages every call, presence and alarm and sends them to the nurse iPads. One server for the whole system.					
		MAIN RACK	1			
				1,00	1.857,14	1.857,14

ACE Business Group International
C/ Colada de Pozuelo, 20
28925 Alcorcón, Madrid (ESPAÑA)
www.acebg.es
CIF: A83706721

CODE	SUMMARY		UNITS	QUANTITY	PRICE	AMOUNT
EOP002	**ud Nurse 10.9" iPad** Nurse station device for receiving, displaying and managing calls: resolves all call types and sets or cancels presence in any room. iPad 10.9" Wi-Fi 128 GB with PVC case, desk stand, adapter and charger.					
		NURSE STATION	1			
				1,00	655,56	655,56
EVV038	**ud Client/Server software Licenses & MDM** ionTab client/server licenses and MDM. Including: nurse iPad, licenses for the NurseCall PCBs of the section, SmartHub and LVNS server. 1st year of software updates included. Quantity per number of PCBs to be confirmed by ACE BG.					
		SYSTEM	1			
				1,00	284,29	284,29
	TOTAL SUBCHAPTER 0102 Digital Room - Shabbat					**6.468,52**
SUBCHAPTER 0103 Network & rack						
ACESWP24P	**ud Switch 10/100 24 PoE ports** Managed PoE switch for the section rack. Connects SmartHub, LVNS server and the nurse station Wi-Fi access point.					
		MAIN RACK	1			
				1,00	287,46	287,46
RACK9U	**ud Wall rack 19" 9U** Wall rack 19" 9U with PDU, shelf and cable management. LOCAL SUPPLY (Orad) – ESTIMATE, TO BE CONFIRMED.					
		MAIN RACK	1			
				1,00	320,00	320,00
UPS1500	**ud UPS 1500 VA online** UPS 1500 VA online, rack mount. LOCAL SUPPLY (Orad) – ESTIMATE, TO BE CONFIRMED.					
		MAIN RACK	1			
				1,00	480,00	480,00

ACE Business Group International
C/ Colada de Pozuelo, 20
28925 Alcorcón, Madrid (ESPAÑA)
www.acebg.es
CIF: A83706721

CODE	SUMMARY	UNITS	QUANTITY	PRICE	AMOUNT
WAP6	**ud Wi-Fi 6 access point, PoE**				
	Wi-Fi access point at the nurse station (if the hospital Wi-Fi is not used).				
	LOCAL SUPPLY (Orad) – ESTIMATE, TO BE CONFIRMED.				
	NURSE STATION	1			
			1,00	220,00	220,00
	TOTAL SUBCHAPTER 0103 Network & rack				**1.307,46**
	TOTAL CHAPTER 01 Yoseftal Eilat. Example Proposal 1. Shabbat option				**14.569,10**
	TOTAL				**14.569,10**

ACE Business Group International
C/ Colada de Pozuelo, 20
28925 Alcorcón, Madrid (ESPAÑA)
www.acebg.es
CIF: A83706721

COMMENTS

IMPORTANT – THIS IS NOT A REAL, FORMAL OR OFFICIAL PROPOSAL. It is an example only, prepared to support the offer that Orad must make to the end client.

Net prices.

Only supply quotation.

Scope (example – to be confirmed by the customer): 8 patient rooms with 3 beds each (24 beds), each room with its own bathroom (washbasin, shower and WC), 1 ward section, 1 nurse station. Shabbat solution.

Bed head: one red nurse call panel with bayonet socket and its pear handset per bed. Presence and call cancellation: one green presence / cancel panel inside each room at the entrance, and one outside each bathroom. Corridor light: above each room door and above each bathroom door. Bathroom: one SOS pull-cord beside the WC and one beside the shower. No Code Blue.

Room controllers (PCB 24 pins, 5 inputs): two per 3-bed room – controller A takes the 3 bed calls, the presence / cancel button at the entrance and the room light; controller B takes the 3 handset disconnection alarms – and one per bathroom (2 SOS pull-cords, presence / cancel outside and the bathroom light). Room controllers connected in daisy chain from the SmartHub of each section with bus cable 2x2x0.8 mm. Maximum number of PCBs per SmartHub bus to be confirmed by ACE BG.

Nurse station: iPad 10.9" (Wi-Fi) with ionTab (Consola Monitor), included with case, desk stand and charger. It receives and resolves all calls and sets or cancels presence in any room.

Network & rack: PoE switch from the ACE BG price list. Rack, UPS and Wi-Fi access point are local supply estimates (yellow) – to be confirmed by Orad.

Not included: cabling, conduits and junction boxes, installation and start-up, hospital LAN / Wi-Fi works, VAT and transport.

Software licences and updates: year 1 included (EVV038); years 2 and 3 to be quoted by ACE BG. Optional full remote support: 15% of the system total per year (2.185,36 € / year).

Recommended spare parts: see the separate spare-parts quotation (1.066,64 €).

See installation scheme ORAD-YOS-EX1-2026-10_esq and plans.

SUBCHAPTER 0101 Nurse Call System	6.793,12 €
SUBCHAPTER 0102 Digital Room - Shabbat	6.468,52 €
SUBCHAPTER 0103 Network & rack	1.307,46 €
TOTAL	**14.569,10 €**

IMPORTANT – THIS IS NOT A REAL, FORMAL OR OFFICIAL PROPOSAL. It is an example only, prepared to support the offer that Orad must make to the end client.

ACE Business Group International
C/ Colada de Pozuelo, 20
28925 Alcorcón, Madrid (ESPAÑA)
www.acebg.es
CIF: A83706721

GENERAL CONDITIONS

The acceptance of the previous Quotation entails the acceptance of the following Conditions.

Any modification must be validated in writing by ACE Business Group.

Currency: EURO

In case of discrepancies in the total calculations, the individual prices of the elements prevail.

INCLUSIONS

Supply and packaging.

Factory configuration, if so specified in each chapter.

The configuration work will be carried out according to availability of the After Sales Department of ACE Business Group.

SCOPE

Factory preconfiguration: Establishment of the specific parameters of the component elements of the system.

Remote Support for Start-up: Specialized assistance to personnel certified by ACE Business Group. Remote connection to high speed Internet is required. Not included in this quotation; to be quoted on request.

Start-up 'ON-SITE': Configuration and commissioning in installations. It is an indispensable condition that all the elements are completely wired and installed. Not included in this quotation; to be quoted on request.

EXCLUSIONS

VAT or other indirect taxes.

International transit excluded. EXW, according to Incoterms 2020.

Wiring costs, installation or commissioning of equipment unless expressly indicated.

VALIDITY OF THE OFFER

Net prices. Validity of the offer of 30 days from the date of this document.

Applicable discounts consult Delegate / Sales Representative.

The discounts do not apply to concepts such as Labor, Start-up and Installation and wiring.

DELIVERY TERM

To be confirmed when placing an order.

BILLING CONDITIONS

Material, interventions of the Technical Department and project documentation will be invoiced upon delivery.

The installation, if applicable, will be billed proportionally to the progress of the work.

PAYMENT METHOD

To be agreed with ACE Business Group in the real proposal.

WARRANTY

All our manufactured products are guaranteed for one year against any malfunction, excluding damages caused by misuse, handling or faulty installation.

The guarantee covers the repair in our warehouses of the defective material, excluding postage.

The displacement of ACE Business Group technical staff is not included.